

SPECIFICATION

MATERIAL	BRIEF SPECIFICATION	Facilities Required
NA	Epoxy encapsulated operating coils control voltage 24 VDC, 72VDC & 110VDC to be used in control gear apparatus for traction application.	In house automatic coil winding machine, no.of turns measurement machine, IR and HV upto 5KV testing facilities. In house epoxy based potting facilities.